

Overview of the KEK Neutrino Beam Facility and its Operation

Summary after September 2000 (NBI2000 @ FNAL)

K.H. Tanaka

for the KEK-PS

Beam Channel Group &
K2K Beam Monitor Group.

March 14th 2002

@NBI2002,

CERN.

Contents

- Introduction
- Performance
- Summary
- Strategy or Future Run Plan

K2K Experiment

The First Long Baseline (250km)
Neutrino Oscillation Experiment



Far Detector: SK
50kt Water C Detector



Shooting Side

- KEK 12GeV PS
- Beam Line
- Beam Facility
- Front Detector

KEK Neutrino Beam Facility




Bird's Eye View of KEK

KEK Neutrino Beam Facility I




Top View

Neutrino Beam Facility II



Side View

Schematic Drawing of the Facility



Primary Proton Beam Line (Extended Part)




Slope (Straight) Section,
5m/72m. 20t Crane is here.



Slope(Straight) Section
ARC Section (No Crane)




Primary Proton Beam Line (N-Hall)



- Small Beam line room, however top can be opened!
- Service tunnel is prepared at downstairs
- Quick disconnect devices of Water&Electricity were developed.

For the Safety Construction & Maintenance





- Often our high-class people says that we should learn Egyptian Technology to save MONEY.
- This may be wrong. We need wider space & Crane to handle highly radioactive beam line elements!

Primary Proton Monitors

- Profile
 - Luminescence Screen (荧光板)
 - SPIC
- Intensity
 - CT
 - SEC

Monitors


	荧光板	SPIC	CT	SEC
- EP1 in	○	○	○	○
- q01 in	○	○	○	○
- q01 out	○	○	○	○
- Col. out	○	○	○	○
- q11 in	○	○	○	○
- b12 out	○	○	○	○
- q12 in	○	○	○	○
- K5 target	○	○	○	○
- BS3 in	○	○	○	○
- q15-q16	○	○	○	○
- K6 target	○	○	○	○
- BS6 in	○	○	○	○
- q18 in	○	○	○	○
- q31 in (T4)	○	○	○	○
- vd1 in	○	○	○	○
- q37-q38	○	○	○	○
- h32 in	○	○	○	○
- q45 out	○	○	○	○
- q49 in	○	○	○	○
- 1st dump	○	○	○	○
- q53 in	○	○	○	○
- q53 out	○	○	○	○
- q57 in	○	○	○	○
- q57 out	○	○	○	○
- q59 in	○	○	○	○
- q59 out	○	○	○	○
- q61 in	○	○	○	○
- q61 out	○	○	○	○
- q65 in	○	○	○	○
- q65 out	○	○	○	○
- b48 out	○	○	○	○
- q68 in	○	○	○	○
- h37 in	○	○	○	○
- v39 out	○	○	○	○
- Target	○	○	○	○
- PPI	○	○	○	○





The Latest Upgrades

- Vacuum system improvement
 - Many vacua Single vacuum section
 - Most Monitors were put into vacuum.
- Magnets were replaced to larger acceptance ones.


Beam Transmission: 5% up





Horns, Target & Decay Volume




- Two Horns (Collector & Reflector).
- Built-in Target in Collector
- 250kA Operation
- 10M Excitation with 30mm Target
- Transformer near-by
- 200m Decay Volume filled with He.




Cross Section
of Collector






Power Supply
for Horns




Neutrino Intensity Enhancement by Horns



Decay Volume & Muon Monitor




Muon/Proton Beam profiles





Proton Profile measured by SPIC.



Muon Profile measured by Muon Chamber and SSD's.



Neutrino Energy (Monte Carlo)



Neutrino Profile (Monte Carlo)



Positioning Precision from KEK to SK

Experimental Requirement:

$\pm 1\text{mrad}$ (Long Term)

- Positioning by GPS and Optical Survey

Horizontal = 1.2m, Vertical = 0.7m,
~ $\pm 0.005\text{mr}$,

- Beam Line Alignment and Monitoring

Horizontal ~ $\pm 0.02\text{mr}$,
Vertical ~ $\pm 0.05\text{mr}$,

- Beam Control and Tuning (Short Term)


Horizontal ~ $\pm 0.03\text{mr}$,
Vertical ~ $\pm 0.06\text{mr}$,

Performance

June 1999 - July 2001

Or, Long Range Beam Stability!?


Delivered Protons on Target (POT)




Date

Goal: 10^{20} POT (for Analysis?)

Muon Profile: Centoroid Stability




Horizontal
+1 mrad
-1 mrad





Vertical
+1 mrad
-1 mrad

Beam Shift Correlation


Profile center history (2000/Jan/14-29)





$X_p^{\text{target}} = \text{Center}$



$X_p^{\text{target}} = 3\text{mm OFF}$




Muon/Proton Correlation



- Horn is -100 times Image Magnifier.
- For accurate aiming, stable positioning of proton beam on target is essential.
- Beam monitors of primary protons are very important.


Front Detector Configuration



1ktWCD: Same Type Detector as SK

MRD and SciFi: Fine Grained Precise Detector

MRD: Massive and Large Solid Angle Detector



Front Detector Photograph

1kt Baby Kamioka

SciFi





Lead Glass

Muon Range
Detector

Front Detector as Neutrino Beam Monitor




Neutrino Beam Profile (MRD)



- One Month Data
- Yellow belt: Fitting Error
- Dot-dashed line: Center from GPS survey


Neutrino Profile: Centroid Stability

(Muon Range Detector)



Horizontal
+1 mrad
-1 mrad

integrated day (1 data point / 5 days)




Vertical
+1 mrad
-1 mrad

integrated day (1 data point / 5 days)

Neutrino Event Rate Stability

(Muon Range Detector/POT)




Horn 250kA Target 30 mm
Horn 200kA Target 20 mm


integrated day (1 data point / 2 days)

Event Number at SK/POT

FC 22.5kt





FC 22.5kt



こるもごろふすみるのふ検定

SK Event: Time Resolution

FC



-0.2 $\mu\text{ sec}$

$$T = T_{\text{sk}} - T_{\text{kek}} - \text{TOF}$$

1.3 $\mu\text{ sec}$

Observed SK events

4.8x10¹⁹pot (Jun99-Jul01)

of observed events and expected events
1999/06-2001/07

	Obs.	No Ocsi.	$\Delta m^2 (\times 10^{-3} eV^2)$		
			3	5	7
FC 22.5kt	56	80.6 ^{+7.3}_{-8.0}	52.4	34.6	29.2
1-ring	32	48.4±6.7	28.1	17.8	16.6
μ -like	30	44.0±6.8	24.4	14.6	13.5
e-like	2	4.4±1.7	3.7	3.2	3.0
multi ring	24	32.2±5.3	24.3	16.8	12.6

Cf. MRD: $87.4^{+12.7}_{-13.9}$ SciFi : $87.3^{+11.9}_{-11.9}$

No oscillation hypothesis is disfavoured at 97% CL.

Summary or Present Status

- Accelerator, Beam channel, Horns, and Beam Monitors are all stable and $\sim 5 \times 10^{19}$ POT was Achieved.
- Excitation number our Magnetic Horns recently exceeded ~ 10 M with 250kA.
- Nice aiming to Super-K continues and we have stable event rate at Super-K.
- Beam side is now OK! We are waiting for the recovery of Super-K.

Strategy of the HORN Operation/Replacement

- September(2002)
 - Replacement of Horns
 - December (2002)
 - SK will re-start with a reduced PMT density
 - 6-7 months Continuous Operation with fast beam
 - 6M Excitation
 - 2.5×10^{19} POT
 - July (2003)
 - Cooling Down
 - Slow Extraction
 - November (2003)
 - Horn Replacement
 - December (2003)
 - 6-7 months Continuous Operation
 - 6M Excitation
 - 2.5×10^{19} POT
 - August(2004)
 - Shut Down for JHF Construction
 - January(2005)
 - Magnet Transfer to Tokai
-