

Acceleration of High-Intensity Protons in the J-PARC Synchrotrons

**KEK/J-PARC
M. Yoshii**

Introduction

- 1. J-PARC consists of 400 MeV Linac, 3 GeV Rapid Cycling Synchrotron (RCS) and 50 GeV Main synchrotron Ring (MR).**
- 2. High Intensity Proton Facility:**

	RCS	MR
Intensity (ppp)	8.3×10^{13}	3.4×10^{14}
Output Beam Power	1 MW	0.73 MW

- 100 times higher than the intensity of KEK-PS (1976-2007)

Features

1. Transition-free lattice

to avoid unwanted beam loss during acceleration.

RCS : a high $\gamma_t = 9.14 > 3$

MR: an imaginary $\gamma_t = j31.6$

Features

1. Transition-free lattice

to avoid unwanted beam loss during acceleration.

RCS : a high $\Upsilon_t = 9.14$

MR: an imaginary $\Upsilon_t = j31.6$

2. Non AC-line synched timing system

to realize the scheduled extraction for multiple Fermi choppers.

Features

1. Transition-free lattice

to avoid unwanted beam loss during acceleration.

RCS : a high γ_t g 9.14

MR: an imaginary γ_t g j31.6

2. Non AC-line synched timing system


to realize the scheduled extraction for multiple Fermi choppers.

3. Magnetic alloy loaded cavity with a full digital LLRF

> achieved high field gradient system (20kV/m)

> realized precise and reproducible fine longitudinal control

Locations of the RCS and MR RF Stations




RF systems are located the place where is the lowest radiation level for hands-on maintenance.

RCS beam commissioning

Energy	400MeV - 3GeV
Intensity	8.3×10^{13} ppp
Power	1000 kW
harmonics / N_b	2 / 2
Frequency	1.23 - 1.67 MHz
# of cavities	12
Peak V_{acc}	450 kV
Cycle	25 Hz

RCS Acceleration pattern



1. RCS rf system: $Q \sim 2$, dual-harmonic ($h=2, 4$) operation.

2. radial feedback: not closed, because it is not necessary.

- stable and reproducible Linac energy and RCS dipole field

- frequency pattern is modified offline.

3. phase feedback: closed for high intensity operation

4. Multi-harmonic RF Feed-forward: ON for each of the cavities.

[Nuclear Instruments and Methods in Physics Research A 621 \(2010\) 15–32,](#)

[“Simulation of longitudinal beam manipulation during multi-turn injection in J-PARC RCS” M. Yamamoto](#)

Beam Injection from the Linac


Linac Beam Pulse : 40 mA, 500 μ s
dp/p , ± 0.03 %

- Chopping by the RCS RF clock
- Chopped pulses are injected into the RCS RF waiting bucket

➡ minimize beam loss during bunching process




- Momentum offset
- Amplitude control for 2nd harmonic RF
- 2nd harmonic phase sweep

➡ increase bunching factor
➡ $B_f > 0.4$ required



Longitudinal painting at J- PARC RCS injection


longitudinal painting using 2nd harmonic voltages



Stable acceleration of 300kW beams in RCS

1. non AC-line synched timing system
2. no radial feedback


Ultra low-jitter extraction (jitter full width: 1deg = 1.7nsec)





Beam phase plot during 1-hour 300kW operation
(190 shots plotted). Right: magnified (19 - 20ms).

MR Design and Operation Modes

- Circumference 1567.5 m
- Three-fold symmetry
- Injection Energy 3 GeV
- Extraction Energy 30 GeV
- Design Beam Power: 750 kW
- The first beam in MR
 - Injection: May 2008
 - Acceleration and extraction: Dec. 2008




- Fast extraction mode (FX) for the neutrino Facility: 1 turn extraction.
- Slow extraction mode (SX) for the hadron hall: 2 s – spill extraction.




MR Beam Power History

- The beam power of 470 kW has been recently achieved with 2.44×10^{14} protons per pulse (ppp) and the cycle time of 2.48 s.
- The designed beam power of 750 kW will be achieved by making the cycle time shorter (1.3 s) and with 2×10^{14} ppp.
- The milestone for the number of accelerated protons has already been passed.



Typical Operation Status for FX

- Power : **471 kW**
- Repetition : **2.48 sec**
- 4 batch (8 bunch) injection during the period of 0.13 s
- **3.1×10^{13} protons per bunch (ppb) \times 8 @ Injection**
- **2.44×10^{14} ppp @ P3 (end of acceleration)**
- Loss during the injection : **220 W**
- Loss in the beginning of acceleration (0.12 s) : **572 W**
- Loss power is within the MR collimator limit of 2 kW
- Loss at 3-50BT : **100 W**, < 3-50BT collimator limit of 2 kW



MR beam commissioning

Energy	3 - 30 GeV
Intensity	2.4×10^{14} ppp
Power	470 kW
harmonics / N_b	9 / 8
Frequency	1.67 - 1.72 MHz
# of cavities (h=9)	7
Peak V_{acc}	300 kV
# of cavities (h=18)	2
Peak V_{acc} (h=18)	110 kV
Repetition (period)	2.48 s/5.52s
Accel. time	1.4 s

1. MR rf system: $Q \sim 25$

Fundamental and 2nd harmonic systems are separated.

2. radial feedback: not closed, because it is not necessary.

- stable and reproducible RCS energy and MR dipole field


- frequency pattern is modified offline.

3. phase feedback: closed.


4. Multi-harmonic RF Feed-forward: ON for each of the cavities.

2nd Harmonic RF Operation



Fundamental 100 kV
 2nd harmonic 0 kV
 Bunching factor
 0.2 ~ 0.3
 Bunch length
 ~200 ns





Fundamental 100 kV
 2nd harmonic 70 kV
 Bunching factor
 0.3 ~ 0.4
 Bunch length
 ~400 ns



Simulation
 (100 kV, 0 kV)




Simulation
 (100 kV, 70 kV)




RF Pattern for operation:
 Injection :
 180 kV (fundamental),
 110 kV (2nd harmonic)
 Acceleration :
 300 kV → 256 kV
 (fundamental)

RF fundamental (kV)




RF 2nd harmonic (kV)



Beam loading issues

- Beam loading by circulating high intensity proton beam of 4.12×10^{13} protons per bunch is the most important issue to be taken into account for stability of the RF system.
- RF system requires both RF beam power and RF generating power to obtain the design gap voltages.
 - ✓ 3.1 MW peak beam power in RCS to obtain by 12 RF systems (255kW)
 - ✓ 2.3 MW peak beam power in MR to obtain by 9 RF systems (250kW)
- For keeping the stability of the system. The relative loading parameter, $Y=I_B/I_0$, is chosen to be smaller than 1 as much as possible.
- MA loaded cavity has a wide-band frequency response. The Q-value is $Q \sim 2$ for the RCS cavity and $Q \sim 25$ for the MR cavity.
- **Multi-harmonic feedforward system** has been developed to compensate the beam induced wake voltages.

Block view of the Multi-harmonic RF Feedforward




- without feedforward

$$V_{\text{cav}}(h, t) = H_{\text{dr}}^{\text{cav}}(h, t) \cdot V_{\text{dr}}(h, t) + Z'_{\text{cav}}(h, t) \cdot I_{\text{beam}}(h, t)$$

The commissioning of the feedforward system is performed for each of the cavities. In the figure, #N is the cavity number.

Block view of the Multi-harmonic RF Feedforward



- without feedforward

$$V_{\text{cav}}(h, t) = H_{\text{dr}}^{\text{cav}}(h, t) \cdot V_{\text{dr}}(h, t) + Z'_{\text{cav}}(h, t) \cdot I_{\text{beam}}(h, t)$$


- with feedforward

$$V_{\text{cav}}(h, t) = H_{\text{dr}}^{\text{cav}}(h, t) \cdot V_{\text{dr}}(h, t) + Z'_{\text{cav}}(h, t) \cdot I_{\text{beam}}(h, t) + Z_{\text{FF}}(h, t) \cdot I_{\text{beam}}(h, t),$$

$$Z_{\text{FF}}(h, t) = -Z_{\text{cav}}(h, t).$$

The commissioning of the feedforward system is performed for each of the cavities. In the figure, #N is the cavity number.

Comparisons of voltage monitor waveforms:
in the cases of no beam, w/o and w/ feedforward



The beam intensity is 300 kW equivalent—(left) middle of acceleration period and (right) just before extraction. The distortion of the voltage waveform is reduced.

Beam loading compensation by multi-harmonic RF feedforward




FIGURE: Frequency-domain
Impedance seen by the beam:
(RCS cavity#1)





FIGURE: Time-domain Impedance
seen by the beam:
(RCS cavity#1)


Impedance at RCS extraction is reduced from **788 Ω** to **10 Ω** .

Beam loading compensation in MR



Mountain Plots of injection beam
(2 bunches)



Longitudinal oscillation during the
acceleration suppressed with FF




dp/p measured by BPM



Longitudinal Oscillations

- Longitudinal oscillations were observed for high beam power of > 470 kW.
- Each bunch seems to have different phase in dipole oscillation.
- A feedback system to suppress the oscillations is in preparation.




Mid-term plan of MR

- Repetition period will be faster, 2.48 s \rightarrow 1.3 s, for the beam power of 750 kW and more.
- Magnet power supplies, rf, injection and extraction devices are being upgraded.

JFY	2015	2016	2017	2018	2019	2020	2021	2022	
		New buildings			Long shutdown				
FX power [kW]	390	470	480-500	> 500	700	800	900	1060	
SX power [kW]	42	42	50	50-60	60-80	80	80-100	100	
Cycle time of main magnet PS	2.48 s			2.48 s	1.3 s	1.3 s	1.3 s	1.3 s	
New magnet PS	Mass production installation/test								
High gradient rf system	Installation							Installation	
2 nd harmonic rf system			Manufacture, installation/test					Manufacture, installation/test	
Ring collimators	Add.collim ators (2 kW)				Add.colli. (3.5kW)				
Injection system	Kicker PS improvement, Septa manufacture /test								
FX system	Kicker PS improvement, FX septa manufacture /test								
SX collimator / Local shields					Local shields				
Ti ducts and SX devices with Ti chamber			ESS						

RF Anode Current as a function of Beam Intensity


- For 1.3 MW, 11 RF cavities and 19-inverter unit modification are necessary.
- For 470 kW, the peak anode current is getting closed to the limit of 15-inverter units.
- Events of serious damages of the inverter units happens more frequently.
- Noise filters were implemented for some of the gate circuits of the inverter units.



ppp (x10 ¹²)	200	240	300	330	#of AccRF	VRF (h=9)	#of 2ndRF	VRF (h=18)
2.48s	390kW	465kW	580kW	640kW	7	280kV	2	110kV

RF Anode Current as a function of Beam Intensity

- For 1.3 MW, 11 RF cavities and 19-inverter unit modification are necessary.
- For 470 kW, the peak anode current is getting closed to the limit of 15-inverter units.
- Events of serious damages of the inverter units happens more frequently.
- Noise filters were implemented for some of the gate circuits of the inverter units.



ppp (x10 ¹²)	200	240	300	330	#of AccRF	VRF (h=9)	#of 2ndRF	VRF (h=18)
2.48s	390kW	465kW	580kW	640kW	7	280kV	2	110kV
1.28s	750kW	900kW	1100kW		9	510kV	2	110kV
1.16s	830kW	1000kW	1.2MW	1.3MW	11	600kV	2	110kV

Summary

- Transition-free lattice and non AC-line synched timing system allow to realize clean and high quality beam operation, which also owes to the stabilities of the Linac energy and Bending field of both synchrotrons.
- By using the MA loaded RF systems,
 - ✓ more than 20 kV/m of high field gradient
 - ✓ Dual harmonic operation in the RCS
 - ✓ No radial tuning loop and the full digital LLRF offer simple, precise and reproducible longitudinal beam control.
 - ✓ Time-jitter of extracted beam from the RCS is only 1.7 ns. Scheduled extraction is possible to the Fermi chopper at the MLF facility.
- Multi-harmonic RF feedforward system has been developed to compensate a heavy beam loading.
 - ✓ The systems are used for the routine operations at RCS and MR and reproducible and offer an excellent suppression of impedance seen by the beam.
- Beam power of 470 kW has been achieved for FX user operation with 2.44×10^{14} protons per pulse (ppp) and the cycle time of 2.48 s.
- The target beam power of 750 kW will be achieved with the faster cycling 2.48 s \rightarrow 1.3 s.